



CITY OF DELTA
PUBLIC WORKS DEPARTMENT
640 W. 4TH STREET
DELTA, COLORADO 81416

WEST LEGACY PARK AT 327 MAIN STREET CDBG # 16-524 PROJECT BID SHEET					
#	DESCRIPTION	QUAN	UNIT	UNIT \$	TOTAL
PARK ENTRANCE FEATURE					
1	REMOVAL OF EXISTING BEAM AND CENTER SUPPORT COLUMN	1	LS		
2	ENTRY COLUMN AND FOUNDATION	2	EA		
3	NEW BEAMS	2	LS		
4	PATCH-CLEANUP OF EXISTING SIDEWALK	1	LS		
GRADING					
5	REMOVAL AND HAUL-OFF EXISTING, UNCLASSIFIED BASE FOR	256	SY		
STORM DRAINAGE					
6	6" S&D DRAINAGE PIPE	140	LF		
7	6" S&D DRAINAGE PIPE FOR FUTURE FOUNTAIN	20	LF		
8	6" S&D WYE FITTINGS	5	LF		
9	4" PERFORATED PIPE IN PLANTERS WITH SOCK	160	LF		
10	DRAIN INLET AT PLAY AREA	2	EACH		
11	6" SQUARE BRASS GRATE DRAIN BASINS IN PAVEMENTS	3	EACH		
12	6" ELL FITTINGS FOR DRAIN BASINS AND DRAIN INLETS AT PLAY	5	EACH		
13	CONNECT TO EXISTING STORM DRAIN INCL. EXCAVATION, ALLEY CUT AND PATCH, BACKFILL	1	LS		
WATER SERVICE					
14	ATTACH TO AND EXTEND SERVICE LINE	100	LF		
ELECTRICAL SYSTEM AND SITE LIGHTING					
15	ELECTRIC SERVICE FROM TRANSFORMER ACROSS ALLEY	1	LS		
16	INCLUDING ALLEY CUT AND PATCH	1	LS		
17	DISTRIBUTION MOUNTING BOARD ON UNISTRUTS	1	LS		
18	1" PVC CONDUITS	640	LF		
19	PEDESTRIAN LIGHTS ON 9 FT POLES	7	EA		
20	GROUND BOXES	6	EA		
21	110v POWER OUTLETS	4	EA		
NEW ENCLOSURE WALLS					
22	NORTH SITE WALL, PILASTERS, STEM WALL, FOOTINGS	1	LS		
PAVEMENTS					
23	CONCRETE PAVEMENT, 6" THICK, INCL 12" STRUCTURAL FILL &	3,235	SF		
24	STAIN FOR RIVER DELTA COLOR	605	SF		
25	STAIN FOR REMAINING PLAZA CONCRETE	2,630	SF		
26	BACK OF PLAY AREA CONCRETE BLOCK/BARRIER	55	LF		
27	TEMPORARY GRAVEL TO COVER GROUND AT FUTURE BATHRO	1,500	SF		
SITE FURNITURE, PLAYGROUND & AMENITIES					
28	BENCHES, SURFACE MOUNT	4	EACH		
29	TRASH / RECYCLE RECEPTACLES, SURFACE MOUNT	2	EACH		
30	BIKE RACKS, PURCHASE AND INSTALL 1, SURFACE MOUNT	1	LS		
31	BIKE RACKS, PURCHASE AND DELIVER TO CITY ONLY	1	LS		
32	PLAYGROUND FILL, 12" DEPTH, FIBAR/PLAYSOFT	30	CY		
33	PLAYGROUND EQUIPMENT - STACKED GFRC TIMBER BALANCE	1	LS		
34	PLAYGROUND EQUIPMENT - 20" BIRCH GFRC STUMPS (5)	1	LS		
35	PLAYGROUND EQUIPMENT - FUN ROCK-SMALL	1	LS		
LANDSCAPE					
36	PLANTER BACKFILL TOPSOIL	43	CY		
37	BOULDERS FOR GROUND LEVEL PLANTERS	20	EA		
38	TREES - EVERGREEN	1	EA		
39	SHRUBS - 5 GAL	12	EA		
40	PERENNIALS - 1 GAL	24	EA		
41	GRASSES - 1 GAL	6	EA		
42	LANDSCAPE SHRUB BED -ROCK MULCH, 3" DEPTH	580	SF		



CITY OF DELTA
 PUBLIC WORKS DEPARTMENT
 640 W. 4TH STREET
 DELTA, COLORADO 81416

WEST LEGACY PARK AT 327 MAIN STREET CDBG # 16-524 PROJECT BID SHEET					
#	DESCRIPTION	QUAN	UNIT	UNIT \$	TOTAL
IRRIGATION					
43	PVC SLEEVING	100	LF		
44	BASIC CONTROLLER	1	EA		
45	NEMA-3 RATED BOX FOR CONTROLLER	1	EA		
46	BACKFLOW PREVENTOR	1	EA		
47	ZONE VALVE	3	EA		
48	1" PVC PIPE	160	LF		
49	COMPRESSION FITTINGS	3	EA		
50	FLUSH BOXES	2	EA		
51	1/2 INCH TUBING	150	LF		
52	XERI SPRAYS, INCLUDING 1/4" DISTIRBUTION TUBING	102	EA		
MISCELLANEOUS					
53	F/A MINOR CONTRACT REVISIONS	1	LS	\$20,000.00	\$20,000.00
TOTAL COST BASE BID:					
BID ALTERNATE					
54	SOUTH MASONARY WALL SURFACE TREATMENT	1,250	SF		
TOTAL COST BID ALTERNATE:					
TOTAL COST BASE BID + BID ALTERNATE:					